

FHWA OFFICE OF OPERATIONS PEER EXCHANGE WORKSHOP

ACCELERATED ROAD WORKS FOR WORK ZONE SAFETY AND MOBILITY

Accelerated Construction Techniques

Jagannath Mallela

June 5-6, 2012

Denver, CO

Accelerated Bridge Construction

Objectives

- The reasons for using ABC/PBES
- Definitions of ABC/PBES
- Benefits of ABC/PBES
- Focus Areas
- The status of EDC deployment goals for ABC/PBES

Reasons for Using ABC

Present & Future Challenges

- Aging Infrastructure
- Increased traffic volumes
 - Freight tonnage
 - Urban capacity
- Rising construction costs
 - \$176B to maintain bridges (2005-2024)
 - \$8.8B annually



Work Zone & Congestion Impacts

Work zone:

- 6,400 work zones (2003)
- 6,157 lane miles closed
- 20% capacity reduction

Congestion:

- Congestion robs our nation of productivity and quality of life
- 4 billion hours/year time delay
- 2.9 billion gallons of wasted gas/year
- \$78.2 billion in 437 urban areas

More Challenges Ahead

- Globalization of manufacturing increases demands on our transportation Intermodal networks
- 1 M more truck traffic by 2016 (ATA)
- More drivers on highways
- Urban Sprawl Continues

Definitions of ABC/PBES

Accelerate Bridge Construction (ABC)

ABC (v): The use of *innovative* planning, design, materials, and construction methods to reduce onsite construction and mobility impact times

PBES are structural components of a bridge that are built offsite, or adjacent to the alignment, and includes features that reduce the *onsite construction time* and *mobility impact time* that occurs from *conventional construction* methods.



expanding the realm of
POSSIBILITY[®]

Benefits of ABC/PBES

Copyright 2009. All rights reserved. Applied Research Associates, Inc.



ARA Proprietary
© 2011 Applied Research Associates, Inc.

Benefits of ABC with PBES

ABC / PBES improves:

Work-zone safety for the traveling public and contractor personnel

Material quality and product durability

Total project delivery time

Site constructability issues

ABC / PBES reduces:

Mobility Impacts

Onsite construction times

Weather-related time delays

ABC / PBES can minimize:

Environmental impacts

Impacts to existing roadway alignment

Utility relocations and right-of-way take





expanding the realm of
POSSIBILITY[®]

FHWA Ever Day Counts ABC Focus Areas

Copyright 2009. All rights reserved. Applied Research Associates, Inc.




ARA Proprietary
© 2011 Applied Research Associates, Inc.




Focus Areas

Foundation & Wall Elements	Rapid Embankment Construction	Prefabricated Bridge Elements & Systems	Structural Placement Methods	Fast Track Contracting
<p>Continuous Flight Auger Piles</p> <p>Geosynthetic Reinforced Soil (GRS) Integrated Bridge System</p> <p>Prefabricated pier cofferdams</p>	<p>EPS Geofoam</p>	<p>Prefabricated Elements</p> <ul style="list-style-type: none"> - Superstructure - Substructure <p>Prefabricated Systems</p> <ul style="list-style-type: none"> - Superstructure - Substructure - Total Bridge 	<p>Self-Propelled Modular Transporters</p> <p>Longitudinal Launching</p> <p>Horizontal Sliding or Skidding</p> <p>Other conventional or heavy lifting equipment or methods</p>	<p>Innovative Contracting</p> <ul style="list-style-type: none"> - Best Value - CMGC method - Design-Build - A+B Bidding - A+B+C Bidding - Warranties

Source: FHWA EDC PBES Initiative



*Prefabricated Cantilever Abutment
(Source: FHWA ABC Manual)*



*Precast Open Frame Pier Bent
(Source: FHWA ABC Manual)*



*Partial Depth Precast Deck
(Source: FHWA Highways for Life)*



*Bridge Move with SPMT
(Source: FHWA Highways for Life)*



Sliding (FHWA HfL)



Bridge Move with SPMT (Mammoet)



Strand Jack Lifting (Mammoet)



expanding the realm of
POSSIBILITY[®]


ABC Decision Framework

Copyright 2009. All rights reserved. Applied Research Associates, Inc.



ARA Proprietary
© 2011 Applied Research Associates, Inc.

Start here



Flowchart

Decision Making

A
T
A
G
L
A
N
C
E



expanding the realm of
POSSIBILITY[®]


The Status of EDC Deployment Goals for ABC/PBES

Copyright 2009. All rights reserved. Applied Research Associates, Inc.




ARA Proprietary
© 2011 Applied Research Associates, Inc.

Pursuing PBES for EDC



Current Status



Copyright 2009. All rights reserved. Applied Research Associates, Inc.

Conclusions

Advantages:

- Faster (offsite & off critical path)
- Safer (public and construction)
- Better Quality (controlled environment)
- Lower Cost (total project/life cycle costs)
- Easily adaptable to many site constraints



Questions?

**FHWA Contacts:
PBES Innovation Team**

Benjamin Beerman, Team Lead
benjamin.beerman@dot.gov

FHWA OFFICE OF OPERATIONS PEER EXCHANGE WORKSHOP

**INNOVATIVE CONTRACTING AND ACCELERATED CONSTRUCTION
TECHNIQUES FOR WORK ZONE SAFETY AND MOBILITY**

**Precast Concrete Pavement Systems for Rapid
Repair, Rehabilitation, and Construction**

**Jagannath Mallela
September 19, 2011
Baltimore, MD**



Accelerated Construction of Concrete Pavements

- Precast Concrete Pavement Systems (PCPS) for concrete pavement construction
 - Momentum is growing
 - Demonstration projects and pilot projects
 - Innovations and modifications
 - Specifications

PCPS Attributes

- Improved quality and performance
- Accelerate construction
- Reduce work zone size and times
- Reduce safety risks
- Reduce risk to contractor and owner agency (use specific terms)
- Extended construction season
- Reduced costs

PCPS Basics

- Fabricated off-site
- Transported to the project site
- Installed on a prepared foundation
- No field curing or time to achieve strength
- Two main categories
 - Jointed Systems – Include system specific joint design
 - Example – Super-Slab and several other generic systems
 - Prestressed Systems – Use a combination of pretensioning (plant during fabrication) and post-tensioning (installation)
 - Example – Precast Prestressed Pavement System (PPCP)




Recent Project Example – I-66 WB, Fairfax, VA



Jointed PCPS - Super-Slab® Pictures

(From I-66 VA and Tappan Zee Toll plaza)






PPCP Pictures (From I-66 VA)




Applications

Slab replacement





Full-depth repair



Conventional paving



Conventional




PCPS

Rehabilitation

Post-tensioning (optional)
New Construction

PCPS General Terminology




States with PCPS Experience




★ HfL projects

★ Other projects

Project Level Decision Logic




Project Level Decision Logic




Project Scope

- Pavement service life and objectives
- Current & projected traffic density
- Slab replacement criteria
- Estimated project duration
- Work window options

Project Level Decision Logic




Pavement Treatment Alternatives



General rules of thumb, based on lane occupancy times

Project Level Decision Logic



Project Specific Considerations

Maintenance
and protection
of traffic

- Need for accelerated construction
 - M&PT considerations, seasonal restrictions, stakeholder impact
- Funding guidelines
- Design and engineering data requirements
- Construction risk
- Specifications

Specification Options


- Sole Source Specification
 - Preselect PCPS system and work directly with provider
- Multiple Source Specification
 - Use PCPS with general performance guidelines
- Generic Specification-Prequalification:
 - Use generic performance specifications = Prequalification of Precast Concrete Paving Systems (www.aashtotig.org)

Prequalification of PCPS Gaining State DOT Approval

- Type of system employed
- Slab thickness
- Slab geometry
- Joint matching needs
- Load transfer
- Reinforcing steel
- Material handling
- Embedment material
- Subgrade requirements
- Bedding requirements
- Pre & post-tension requirements
- Surface texture
- Ride quality
- Load transfer efficiency
- Slab installation procedures

**Trial installations - prove the PCPS
off-site - before the project begins**

Project Level Decision Logic




Construction Considerations

- Qualified precaster presence in area
- Contractor's familiarity with PCPS construction process
- Planning and scheduling
- Quality assurance
- Contract plans



Project Level Decision Logic



Cost Considerations

- Should expand beyond initial costs
- LCCA - reduced maintenance costs and user-delay cost
- MTO reports only 10% higher cost than high early strength
- Economies of scale and industry familiarity
- Considerations of Road User Costs appropriate

PCPS Summary

- Successful installations nationwide
- Proven long term performance
- Ideal for accelerated construction for projects with lane closure restrictions
- Specification and guidelines available for your use
- PCPS can be added to your PCC treatment toolbox



Thank you!!

Jagannath Mallela
ARA, Inc.
(217) 356-4500
jmallela@ara.com

